



Problem: Lake Water Level

- Increasing periods of "No Wake"
- Localized flooding more frequent
- Unknown effectiveness of lake outfall










Answer: Assess & Propose Solution


- Analyze Existing Outfall Structure
 - Find Suitable Model
 - Calibrate to observed HWL's
- Propose Retrofit






Lake Background: Location Map





Lake Background: Bathymetric Map





Lake Background: Lake Schematic






Model: Analysis & Calibration

- EPA SWMM was the chosen model
 - Allowed for analysis of culverts with impact of downstream dam
 - Collected field surveyed data for input
 - Calibrated to observed HWL to maximum extent possible
 - Used calibrated model to propose a retrofit for better outfall functionality
- Reviewed results with LLMD staff
- Incorporated any information from previous WDNR reports




Model: Drawdown Curves





Model: Drawdown Curves





Model: Result

- Settled on (2) 5' X 3' box culvert
- Began permitting process through Wisconsin DNR, Walworth Co, and USACE
- WDNR "Minor Replacement" as described under Trans 207.04.
- Walworth Co Land disturbance permit
- USACE Statewide permit for restorative work within a navigable waterway



Problem: Lake Delton

Lake Delton collapse in June 2008 caused WDNR to reassess all existing dam safety related issues





Problem: Lake Delton

- WDNR performed a dam safety inspection which further resulted in:
 - Dam Breach Analysis
 - Emergency Action Plan (EAP)
 - Operation and Maintenance (O&M) Schedule
 - Analysis of 1,000 year flow on proposed structure
- Additional requirements delayed acceptance of the construction plans by up to 8 months




Construction: Demolition & Replacement

- Staging
- Demolition
- Dewatering









Construction: Stuff Happens

- Contractor Locates Gas Main
- Emergency Coordination
- Emergency Removal







Construction: Cooler Heads Prevail

- We Energies handles everything within days
- Dewatering completed
- Culvert installation completed







Construction: Box Culvert

- Staged box culvert installation
- Dewatering reversal
- Restoration










When something goes awry...blame the engineer







Models are not real. They are a representation of false reality under ideal conditions.



Communication is key to solving problems and moving forward to adversity







Making a complete diagnosis of the problem can't always be completed until the project is over.







YOU can help your lake to get better. If you thing something is wrong don't wait to prove yourself right.







Summary

- Increased volume due to increased impervious cover
- Increased restriction at outlet due to zebra mussel colonization
- Retrofit of outfall to allow for restriction at dam and maintenance at culvert crossing
- Lake Management District Staff to investigate potential watershed management action plan to help incorporate better development standards

